No.	Items of work	Per	Rate			Quantity	Cost	Total
	Excavating weir halla up to Voddar Vanka feeder.—		Rs.	a.	p.		Rs.	
1	Earthwork excavation	C.yd.				2,717		
2	Do to bank with watering and tamping including lead and lift from the selected site.	,,				2,278		
3.	New stone work	,,				665		
	Total ...	...				...		

Notice dated 17th May 1929.

The attention of the Public is invited to the Notification published in the *Mysore Gazette*, Part VI, pages 470 and 471, dated 23rd May 1929, calling for tenders for increasing the capacity of Pombarahalli Byalakere Tank, Mulbagal Taluk. Last date of tender is 8th June 1929.

Notice dated 17th May 1929.

The attention of the public is invited to the Notification published in the ***Mysore Gazette***, Part VI, pages 469 and 470, dated 23rd May 1929, calling for tenders for restoring Bairanahalli Shekmanpur Tank, Malur Taluk. Last date of tender is 8th June 1929.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification.

Attention is invited to the publication notified in the *Mysore Gazette*, Part VI, pages 471 to 477, dated 23rd May 1929, tenders for constructing Dalvoy tank near Singadahalli, Chiknayakanhalli Taluk.

Last date for presentation of the tender is 12th June 1929 up to 2 P.M.

V. V. PATANKAR,
Executive Engineer.

HASSAN DIVISION.

Notice dated 17—18th May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hasan Division, up to 2 P.M., on 6th June 1929, for constructing Middle School building at Anekere Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees 50 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Middle School building at Anekere, Channarayapatna Taluk", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate for constructing a Middle School Building at Anekere, Channarayapatna Taluk, for 1928-29:—

Serial No.	Items of work	Per	Quantity	Remarks
	MAIN BUILDING.			
1	Earthwork excavation and filling in basement ...	C.yd.	18	
2	Filling foundation with stone in clay	C.ft.	488	
3	Filling basement with stone in clay	,,	268	
4	Burnt brick in clay superstructure	,,	658	
5	Burnt stone slabs 6" thick dressed and fixed ...	Sqr.	69	
6	Honne wood work, wrought and put up ...	C.ft.	64·02	
7	Roofing with 1st Class Mangalore tiles, on teak reepers, nails, etc., complete.	Sqr.	10·29	
8	Ridge tiles set in mortar	R ft.	86	
9(a)	Chunam plastering rough	Sqr.	13·50	
(b)	Do nice	,,	2·04	
10	Honne wood battened doors complete	S.ft.	18	
11	Do windows complete ...	,,	26	
12	Honney comb ventilators including wire net fixed outside.	,,	32	
13	White washing two coats	,,	15 50	
14	Chunam pointing to basement	,,	2·00	
15	Gravelling the floor	,,	3·30	
16	Flooring with concrete including plastering ...	,,	1·80	
17	Chacolate painting	,,	1·00	
18	Providing gates	,,	24	
19	Tarring	Lump	sum	
20	Teakwood eave board	R.ft.	132	
21	Clearing site	Lump	sum	
	COMPOUND WALL.			
1	Earthwork excavation for foundation	C.yd.	4	
2	Filling in foundation as per excavation with rough stone in clay basement and pillar ...	C.ft.	170	
3	Burnt brick in mud superstructure	,,	174	
4	Do coping with plastering	R.ft.	54	
5	Chunam plastering	Sqr.	4 75	
6	Gate	Lump	sum	
7	Unforeseen charges	,,	,,	

Dated 17—18*th May* 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 2 P.M., on 6th June 1929, for constructing Middle School Building at Grama, Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Middle School Building at Grama, Hassan Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor, will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be ferfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate for constructing a Middle School Building at Grama, Hassan Taluk, for 1928-29.

No.	Items of work	Per	Quantity
	Main Building.		
1	Earthwork excavating and filling in basement	C.yd.	18
2	Filling foundation with stone in clay	C.ft.	488
3	Filling basement with stone in clay	,,	268
4	Burnt brick in clay superstructure	,,	658
5	Burnt stone slabs 6" thick dressed and fixed	Sqr.	69
6	Honne wood work, wrought and put up	C.ft.	64·02
7	Roofing with 1st class Mangalore tiles, on teak reepers, nails, etc., complete.	Sqr.	10·29
8	Ridge tiles set in mortar	R.ft.	86
9 (a)	Chunam plastering rough	Sqr.	13·50
(b)	Do nice	,,	2·04
10	Honne wood battened doors complete	S.ft.	18
11	Do do windows complete	,,	26
12	Honney comb ventilators including wire net fixed outside ...	,,	32
13	White washing two coats	,,	15·50
14	Chunam pointing to basement	,,	2·00
15	Gravelling the floor	,,	3·30
16	Flooring with concrete including plastering	,,	1·80
17	Chacolate painting	,,	1·00
18	Providing gates	,,	24
19	Tarring	Lump	sum.
20	Teakwood eave board	R.ft.	132
21	Clearing site	Lump	sum
	Compound Wall.		
1	Earthwork excavation for foundation	C.yd.	4
2	Filling in foundation as per excavation with rough stone in clay basement and pillar.	C.ft.	170
3	Burnt brick in mud superstructure	,,	174
4	Do coping with plastering	R.ft.	54
5	Chunam plastering	Sqr.	4·75
6	Gate	Lump	sum
7	Unforeseen charges	Lump	sum

Notice dated 18th May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer Hassan Division, up to 2 P.M. on 6th June 1929, for constructing Urdu Middle School, Building at Hole-Narsipur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 50 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing Urdu Middle School, Building at Hole-Narsipur", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancalled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding, the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

Estimate for constructing a Middle School Building (Urdu) at Hole-Narsipur for 1928-29.

No.	Items of work	Per	Quantity
	Main Building.		
1	Earthwork excavation and filling in basement ...	C.yd.	18
2	Filling foundation with stone in clay	C.ft.	488
3	Filling basement with stone in clay	,,	268
4	Burnt brick in clay superstructure	,,	653
5	Burnt stone slabs 6" thick dressed and fixed	Sqr.	69
6	Honne wood work, wrought and put up	C.ft.	64·02
7	Roofing with 1st Class Mangalore tiles on teak reepers, nails etc., complete.	Sqr.	10·29
8	Ridge tiles set in mortar	R.ft.	86
9 (*a*)	Chunam plastering (rough)	Sqr.	13·50
(*b*)	Do (nice)	,,	2·04
10	Honne wood battened doors complete	S.ft.	18
11	Do do windows complete ...	,,	26
12	Honney comb ventilators including wire net fixed outside ...	S.ft.	32
13	White washing, 2 coats	,,	15·50
14	Chunam pointing to basement	,,	2·00
15	Gravelling the floor	,,	3·30
16	Flooring with concrete including plastering	,,	1·80
17	Chacolate painting	,,	1·00
18	Providing gates	,,	24
19	Tarring	L. S.	...
20	Teakwood eave board	R.ft.	132
21	Clearing site...	L. S.	...
	Compound Wall.		
1	Earthwork excavation for foundation	C.yd.	4
2	Filling in foundation as per excavation with rough stone in clay basement and pillar.	C.ft.	170
3	Burnt brick in mud superstructure	,,	174
4	Do coping and plastering	R.ft.	54
5	Chunam plastering	Sqr.	4·75
6	Gate	L. S.	..
7	Unforeseen charges	L. S.	...

Notification dated 18th May 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 2 P.M.; on 6th June 1929, for constructing a Middle School Building at Hirisave, Channarayapatna Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 50 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Middle School Building at Hirisave, Channarayapatna Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Estimate for constructing a Middle School Building at Hirisave, Channarayapatna Taluk, for 1928-29 :—

No.	Items of work	Per	Quantity
	MAIN BUILDING.		
1	Earthwork excavation and filling in basement	C.yd.	18
2	Filling foundation with stone in clay	C.ft.	488
3	Filling basement do	,,	268
4	Burnt brick in clay superstructure	,,	658
5	Burnt stone slabs 6" thick dressed and fixed	S.qr.	69
6	Honne wood work, wrought and put up	C.ft.	64·02
7	Roofing with First Class Mangalore tiles, on teak reepers, nails, etc., complete.	Sqr.	10·29
8	Ridge tiles set in mortar	R.ft.	86
9 (a)	Chunam plastering rough	Sqr.	13·50
(b)	Do nice	,,	2·04
10	Honne wood battened doors complete	S.ft.	18
11	Do windows complete	,,	26
12	Honney comb ventilators including wire net fixed out side ..	,,	32
13	Whitewashing two coats	,,	15·50
14	Chunam pointing to basement	,,	2·00
15	Gravelling the floor	,,	3·30
16	Flooring with concrete including plastering	,,	1·80
17	Chacolate painting	,,	1·00
18	Providing gates	,,	24
19	Tarring	Lump sum	
20	Teakwood eave board	R.ft.	132
21	Clearing site	Lump sum	
	COMPOUND WALL.		
1	Earthwork excavation for foundation	C.yd.	4
2	Filling in foundation as per excavation with rough stone in clay basement and pillar.	C.ft.	170
3	Burnt brick in mud superstructure	,,	174
4	Do coping with plastering	R.ft.	54
5	Chunam plastering	Sqr.	4·75
6	Gate	Lump sum	
7	Unforeseen charges	Lump sum	

N. KRISHNIENGAR,
Executive Engineer.